

PERMIT
INFORMATION
PACKET

Pelican River Watershed District

211 Holmes St W, Suite 201, P.O. Box 1043, Detroit Lakes, MN 56502
(218) 846-0436 phone (218) 846-0778 fax
www.prwd.org

Alterations within the Bluff Impact Zone or on Steep Slopes in the Shoreland District PERMIT INFORMATION

Use this packet for preparation of an application for actions involving land, vegetative, or impervious surface alterations within a bluff impact zone or on steep slopes within the Shoreland District.

Complete and sign enclosed applications to the District office for review and approval. Applications must be signed by the property owner or governmental unit (if applicable). Complete applications will include: (1) signed application; (2) necessary maps, diagrams and any necessary product specifications or calculations in duplicate; and (3) permit application/field inspection fees. Additional information may be required by the District after initial review.

Applications are usually reviewed within 14 days, however the District reserves the right to allow 60 days for approval from receipt of completed application. Once all plans and other permit requirements are met, the Board of Managers or their Designee will approve your permit. You can pick up the signed permit at the District office or we can mail it to you by request. PRWD Staff will inform you within ten (10) days written notice of any deficiencies in your application and ask you to make necessary changes.

In reviewing and approving applications, the following will be taken into consideration:

General Conditions:

The action will not result in increases in stormwater discharge rates to adjoining properties or to waters of the state for the 5-year, 25-year, and 100-year- 24-hour rainfall events and must utilize standards procedures for controlling runoff rates, nutrients, and sediments.

For development adjacent to a bluff or steep slope, drainage from hard surfaces should direct runoff away from the bluff or steep slope.

Proposed actions involving bluff impact zones or on steep slopes within the Shoreland District must include with the signed permit application the following :

- A. Grading and Sediment Erosion Control Plan
- B. Site evaluation and construction plans designed and signed by an appropriate registered professional .
- C. A soils engineering or geological report if requested by the District.

Shoreland District or Zone: land located within 1,000 feet of the ordinary high water mark of a lake, pond, or 300 feet from a river or stream, as defined in the Becker County Zoning Ordinance.

Shore Impact Zone (setback from ordinary high water level):
General development lake— 37.5 feet; Recreational development lake— 50 feet; Environmental Development Lake—75 feet; unsewered rivers—50 feet; sewerred rivers— 37.5 feet

Steep slope: steep slopes, that are not bluffs, are lands having average slopes more than 12 percent, as measured over distances of 50 feet measured on the ground.

Bluff Impact Zone: Hill, cliff or embankment located within the shoreland area and draining to a water body, having a slope rising at least 25 feet above the ordinary high water level of the waterbody and where the grade of the slope from the toe of the bluff to any point 25 feet or more above the OHW averages 30% or greater and the land located within 20ft from the top of the bluff.

**PERMIT
INFORMATION
PACKET**

Pelican River Watershed District

211 Holmes St W, Suite 201, P.O. Box 1043, Detroit Lakes, MN 56502
(218) 846-0436 phone (218) 846-0778 fax
www.prwd.org

GRADING & EROSION CONTROL PLAN

EROSION & SEDIMENT CONTROL PLAN

The goal of this plan is to prevent erosion from occurring and keep sediment on the site during active construction.

This is accomplished by minimizing: (1) the area and duration of exposed soil and unstable soil conditions; (2) off-site sediment transport on trucks and equipment; (3) work in and adjacent to water bodies and wetlands; (4) soil compaction. In addition, maintain stable slopes, and avoid steep slopes and the need for high cuts and fills.

Natural site topography and soil conditions must be considered to reduce erosion and sedimentation during construction and after project completion. Erosion and sediment control measures must be installed prior to land altering activities and routinely inspected and maintained during the project until final turf and ground cover has been established. The project site must be inspected after every rainfall event exceeding 0.5 inches and implement erosion and sediment control measures as addressed as needed. The project must be phased as best as possible to minimize disturbed areas and removal of existing vegetation until necessary for project progress. In order to ensure that sediment is retained on-site, the District may require the permit applicant to provide additional erosion control measures where site conditions warrant. Temporary erosion and sediment control measures (i.e., silt of land alteration. For areas altered with a slope of 3:1 or greater, restoration with sod or woofence, rock access drives) must be removed after all disturbed areas have been stabilized.

All disturbed areas must be restored at a minimum with seed and disced mulch, sod, wood-fiber blanket, or be hard surfaced within 2 weeks from the completion d fiber blanket is required. Typically, restoration with seed and disced mulch must be completed not later than September 15. Areas to be restored with sod must be completed by October 15. Both of these restoration dates are in accordance with Natural Resource Conservation Service requirements.

EROSION AND SEDIMENT CONTROL PLAN MUST INCLUDE:

1. Existing and proposed topographic map which clearly indicates all hydrologic features(i.e., ditches, grass channels, swales, perennial/intermittent streams, wetlands, lakes, ponds, floodplains, culverts, and storm sewers) and areas where grading will expose soils to erosive conditions. The plan must also indicate the direction of all site runoff.
2. Identification of all temporary erosion control measures which will remain in place until permanent vegetation is established for the construction site, including entryways onto sites and for work areas within open water. Examples include, but are not limited to: seeding, mulching, sodding, silt fence, erosion control matting, access drives (rocked filter dike at construction site entrance). Work proposed within open water areas (e.g., installation of a storm sewer outfall) floatation silt curtain must be used.
3. Location and dimensions of all temporary soil or dirt stockpiles.
4. A detailed schedule indicating dates and sequence of land alteration activities; implementation, maintenance and removal of sediment and erosion control measures; and permanent site stabilization measures.
5. Name, address, and phone number of party responsible for maintenance of all erosion control measures.
6. A detailed description of how erosion control, sediment control and soil stabilization measures implemented pursuant to the plan will be monitored, maintained, and removed.
7. Identification of all permanent erosion control measures such as vegetation, outfall spillways, and rip-rap shoreline protection, and their locations.
8. Copy of MPCA Notification of application for an NPDES general permit for projects one acre or more of graded area.
9. Tabulation of all earthwork cut-and-fill volumes and computation of any floodplain volume and/or wetland area changes.

All actions and plans must utilize standards and procedures for controlling runoff rates, nutrients, and sediments as described in the "Protecting Water Quality in Urban Areas" manual (MPCA , 2000) as revised.